BRUHAT BANGALORE MAHANAGARA PALIKE

Name of Work:Modified Estimate for Package No.05 (Consists of 3 Works)

Sl No	Description of work	No	Length m	Breadth m	Depth m	Quantity	Unit	Rate in Rs	Amount in Rs
1	Removing & Resetting of cover Slabs of drains and pointing in CM 1:2.								
	Ramchandrapura								
	Gangamma Temple Rd	2	235.50	0.75		353.25			
						353.25	**Cum**	**127.03**	**44873.35**
	Approved Amount		**127.03**						
2	Earth work excavation by manual means for drains,canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such simillar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50								
	RCC Drain								
	Shimadri Layout								
	1st Cross Rd	2	101.50	1.10	1.00	223.30			
	2nd Cross Rd	2	65.50	1.00	1.00	131.00			
	3rd Cross Rd	2	107.50	1.00	1.00	215.00			
	4th Cross Rd	2	56.60	1.00	1.00	113.20			
	5th Cross Rd	2	56.20	1.00	1.00	112.40			
	Singapura Paradise								
	6th Main Rd	2	144.80	1.10	1.00	318.56			
	Culvert	2	5.30	1.50	1.00	15.90			
	Drain Desilt								
	Ramchandrapura								
	Gangamma Temple Rd	2	235.50	0.45	0.50	105.98			
	Sri Balaji Layout (Singapura								
	2nd Cross Rd	2	62.50	0.45	0.40	22.50			
	3rd Cross Rd Left Side Rd	2	52.50	0.45	0.40	18.90			
	3rd Cross Rd Right Side Rd	2	44.00	0.45	0.35	13.86			
	4th Cross Rd Right Side Rd	1	24.00	0.45	0.30	3.24			
	4th Cross Rd Left Side Rd	2	46.00	0.45	0.40	16.56			
	Varadharaj Nagara								
	3rd Main Rd	2	285.00	0.45	0.35	89.78			
	Aveksha Hospital Rd	2	80.00	0.45	0.35	25.20			
	4th A Cross Rd	1	40.00	0.45	0.35	6.30			
	3rd A Cross Rd	1	35.00	0.45	0.35	5.51			
	2nd A Cross Rd	1	45.00	0.45	0.35	7.09			
	Singapura Paradies								
	2nd Main Rd	1	35.00	0.45	0.40	6.30			
	1st Main Rd	2	106.00	0.45	0.35	33.39			
	1st Main 1st Cross Rd	1	22.00	0.45	0.40	3.96			
	Ganesha Layout								
	Main Rd	2	98.00	0.45	0.40	35.28			
	Burm Cutting								
	Singapura Paradies								
	6th Main Rd	2	146.50	0.60	0.35	61.53			
	5th Main Rd	2	137.10	0.55	0.30	45.24			

Sl No	Description of work	No	Length m	Breadth m	Depth m	Quantity	Unit	Rate in Rs	Amount in Rs
	4th Min Rd	2	147.00	0.50	0.35	51.45			
	2nd Main Rd	2	162.00	0.55	0.30	53.46			
	1st Main Rd	2	165.00	0.60	0.30	59.40			
	1st Main 1st Cross Rd	2	110.50	0.55	0.35	42.54			
	1st Main 2nd Cross Rd	2	108.90	0.55	0.30	35.94			
	1st Main 3rd Cross Rd	2	125.30	0.55	0.35	48.24			
	New Sai Garden					0.00			
	4th Cross Rd	2	58.30	0.50	0.35	20.41			
	3rd Cross Rd	2	54.30	0.55	0.30	17.92			
	2nd Cross Rd	2	47.50	0.60	0.35	19.95			
	Ganesh Layout					0.00			
	3rd Cross Rd	2	120.40	0.55	0.30	39.73			
	4th Cross Rd	2	115.50	0.50	0.35	40.43			
	Main Rd	2	336.50	0.55	0.35	129.55			
	7th Main Rd	2	55.40	0.60	0.30	19.94			
	6th Main Rd Right Side Rd	2	46.20	0.50	0.30	13.86			
	6th Main Rd Left Side Rd	2	47.00	0.60	0.35	19.74			
	5th Main Rd Left Side Rd	2	36.30	0.50	0.30	10.89			
	5th Main Rd Right Side Rd	2	47.50	0.50	0.30	14.25			
	4th Main Rd Right Side Rd	2	48.90	0.40	0.30	11.74			
	2nd Main Rd Right Side Rd	2	48.90	0.65	0.30	19.07			
	Sri Balaji Layout (Singapura Bus Stop)								
	2nd Cross Rd	2	89.30	0.50	0.35	31.26			
	3rd Cross Rd Left Side Rd	2	76.60	0.60	0.35	32.17			
	3rd Cross Rd Right Side Rd	2	75.20	0.50	0.30	22.56			
	4th Cross Rd Right Side Rd	2	24.70	0.50	0.30	7.41			
	4th Cross Rd Left Side Rd	2	63.70	0.65	0.30	24.84			
	Main Rd	2	123.50	0.50	0.30	37.05			
	Singapura Layout								
	1st Cross Rd	2	70.80	0.55	0.35	27.26			
	2nd Cross Rd	2	121.30	0.55	0.30	40.03			
	3rd Cross Rd	2	185.60	0.55	0.30	61.25			
	4th Cross Rd	2	213.40	0.55	0.30	70.42			
	5th Cross Rd	2	230.50	0.50	0.35	80.68			
	6th Cross Rd From End	2	266.10	0.50	0.30	79.83			
	Cross Rd-1	2	34.70	0.50	0.30	10.41			
	5th A Cross Rd	2	96.00	0.60	0.30	34.56			
	Patanjali Shop Rd	2	144.40	0.50	0.30	43.32			
	Cross Rd-6	2	20.50	0.65	0.30	8.00			
	Cross Rd-5	2	16.00	0.55	0.40	7.04			
	Cross Rd-4	2	22.20	0.70	0.30	9.32			
	Cross Rd-3	2	24.90	0.50	0.30	7.47			
	Cross Rd-2	2	22.00	0.45	0.30	5.94			
	Cross Rd-1	2	22.70	0.60	0.40	10.90			
	3rd Main Rd	2	178.00	0.55	0.35	68.53			
	2nd Main Rd	2	395.30	0.60	0.30	142.31			
	Cross Rd-7	2	27.30	0.50	0.30	8.19			
	1st Main Rd from end	2	438.00	0.55	0.30	144.54			
	Cross Rd-8	2	27.50	0.50	0.40	11.00			
	Cross Rd-9	2	27.00	0.70	0.30	11.34			

Sl No	Description of work	No	Length m	Breadth m	Depth m	Quantity	Unit	Rate in Rs	Amount in Rs
	Kamaru House Rd	2	291.50	0.55	0.30	96.20			
	Muniswamappa Garden								
	6th Main Rd	2	208.00	0.55	0.35	80.08			
	1st Main Rd	2	112.00	0.60	0.30	40.32			
	Cross Rd-1	2	35.30	0.60	0.30	12.71			
	Cross Rd-2	2	50.00	0.50	0.30	15.00			
	Cross Rd-3	2	37.00	0.55	0.35	14.25			
	Cross Rd-4	2	51.40	0.60	0.30	18.50			
	Cross Rd-5	2	53.00	0.50	0.30	15.90			
	Cross Rd-6	2	81.70	0.60	0.30	29.41			
	Cross Rd-7	2	42.70	0.55	0.30	14.09			
	Acchi Store Rd	2	138.60	0.55	0.30	45.74			
	Kuvempu Nagara 2nd Stage								
	Thetar Gate Opposite Rd	2	73.50	0.55	0.30	24.26			
	Varadharaju Nagara								
	1st Cross Rd Left Side	2	61.00	0.50	0.40	24.40			
	1st Cross Rd Right Side	2	35.50	0.70	0.35	17.40			
	2nd Cross Rd Left Side	2	63.60	0.55	0.30	20.99			
	2nd Cross Rd Right Side	2	22.60	0.55	0.45	11.19			
	3rd Cross Rd Left Side	2	66.00	0.60	0.35	27.72			
	4th Cross Rd Left Side	2	65.50	0.55	0.40	28.82			
	6th A Cross Rd	2	78.00	0.50	0.45	35.10			
	4th A Cross Rd	2	81.00	0.65	0.30	31.59			
	3rd A Cross Rd	2	82.80	0.55	0.35	31.88			
	2nd A Cross Rd	2	84.00	0.60	0.40	40.32			
	1st A Cross Rd	2	71.00	0.55	0.30	23.43			
	5th Cross Rd Right Side	2	238.00	0.55	0.35	91.63			
	1st Cross A Cross Rd	2	18.00	0.65	0.40	9.36			
	Axis Bank Opposite Rd	2	152.50	0.50	0.30	45.75			
	Singapura Garden								
	4th D Cross Rd	2	119.70	0.60	0.30	43.09			
	Vasbalanagara								
	5th Cross Rd	2	145.00	0.60	0.35	60.90			
	Thirumala Store Rd	2	86.00	0.65	0.45	50.31			
	3rd Main 5th Cross Rd	2	538.50	0.55	0.40	236.94			
	Cross Rd	2	194.50	0.50	0.35	71.20			
						4644.55	**Cum**	**214.79**	**997602.93**
	Approved Amount	**214.79**							
3	Providing of Precast slab of 10CM thick for Drains								
	RCC Drain								
	Shimadri Layout								
	1st Cross Rd	2	101.50	0.90		182.70			
	2nd Cross Rd	2	65.50	0.75		98.25			
	3rd Cross Rd	2	107.50	0.75		161.25			
	4th Cross Rd	2	56.60	0.75		84.90			
	5th Cross Rd	2	56.20	0.75		84.30			
	Singapura Paradise								
	6th Main Rd	2	144.80	0.90		261.18			
						872.58	**Sqm**	**2175.19**	**1898029.09**
	Approved Amount	**2175.19**							

Sl No	Description of work	No	Length m	Breadth m	Depth m	Quantity	Unit	Rate in Rs	Amount in Rs
4	Providing of Precast slab of 23CM thick for Culverts								
	RCC Drain								
	Culvert	2	5.30	1.20		12.60			
						12.60	**Sqm**	**5287.84**	**66627.05**
	Approved Amount		**5287.84**						
5	Removing and resetting of kerb stones								
						0.00	**Sqm**	**123.88**	**0.00**
	Approved Amount		**123.88**						
6	Providing and fixing pre cast solid cement concrete kerb stones made out of M20 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation ete.,complete as directed by the Engineer in Charge of the work								
						0.00	**Nos**	**585.47**	**0.00**
	Approved Amount		**585.47**						
7	Painting Two Coats on New Concrete Surfaces Painting two coats after filling the surface with synthetic enamel paint in all shades on new plastered concrete surfaces								
						0.00	**Sqm**	**98.16**	**0.00**
	Approved Amount		**98.16**						
8	Providing and constructing load bearing wall with Solid Concrete blocks of size 400x150x200mm having block density more than 1800kg/m3 and minimum compressive strength of 4.00 N/mm2 conforming to IS 2185 (Part - I) - 2005 and constructed with CM 1:4 as per IS 2572:2005 including cost of all materials, labour, scaffolding and curing, usage charges of machinery etc complete as per specifications								
						0.00	**Sqm**	**1225.22**	**0.00**
	Approved Amount		**1225.22**						
9	Scarifying the existing bituminous road surface to a depth of 50 mm and disposal of scarified material by Mechanical Means using Hydraulic excavator with in all lifts and lead								
						0.00	**Sqm**	**4.62**	**0.00**
	Approved Amount		**4.62**						

Sl No	Description of work	No	Length m	Breadth m	Depth m	Quantity	Unit	Rate in Rs	Amount in Rs
10	Earth work in surface excavation for stripping, seating of bund, Road way by manual means for lowering & levelling the ground for all works other than foundation & depth in Ordinary rock and soft rock upto 300mm depth as per drawing and technical specifications, including setting out, barricading, caution lights, including dressing of excavated surfaces, disposing off or levelling the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools, usage& other appurtenances required to complete the work.								
	Asphalt Road								
	Edge Correction/Cut Portion								
	Singapura Paradies								
	Singapura Paradies								
	6th Main Rd	1	146.50	0.95	0.20	27.84			
	5th Main Rd	1	137.10	0.90	0.20	24.68			
	4th Min Rd	1	147.00	1.00	0.20	29.40			
	2nd Main Rd	1	161.00	1.00	0.20	32.20			
	1st Main Rd	1	165.00	1.15	0.20	37.95			
	1st Main 1st Cross Rd	1	110.50	1.10	0.20	24.31			
	1st Main 2nd Cross Rd	1	108.90	1.15	0.20	25.05			
	1st Main 3rd Cross Rd	1	125.30	1.05	0.20	26.31			
	New Sai Garden								
	4th Cross Rd	1	58.00	6.00	0.20	69.60			
	3rd Cross Rd	1	54.30	5.70	0.20	61.90			
	2nd Cross Rd	1	47.50	5.70	0.20	54.15			
	Ganesh Layout								
	3rd Cross Rd	1	120.40	2.00	0.20	48.16			
	4th Cross Rd	1	115.50	1.05	0.20	24.26			
	Main Rd	1	336.50	1.00	0.20	67.30			
	7th Main Rd	1	55.40	0.70	0.20	7.76			
	6th Main Rd Right Side Rd	1	46.20	0.70	0.20	6.47			
	6th Main Rd Left Side Rd	1	47.00	0.80	0.20	7.52			
	5th Main Rd Left Side Rd	1	36.30	0.80	0.20	5.81			
	5th Main Rd Right Side Rd	1	47.50	0.80	0.20	7.60			
	4th Main Rd Right Side Rd	1	48.90	0.70	0.20	6.85			
	2nd Main Rd Right Side Rd	1	48.90	0.80	0.20	7.82			
	Sri Balaji Layout (Singapura Bus Stop)								
	2nd Cross Rd	1	89.30	6.15	0.20	109.84			
	3rd Cross Rd Left Side Rd	1	76.60	6.50	0.20	99.58			
	3rd Cross Rd Right Side Rd	1	75.00	6.30	0.20	94.50			
	4th Cross Rd Right Side Rd	1	24.50	6.00	0.20	29.40			
	4th Cross Rd Left Side Rd	1	63.70	5.30	0.20	67.52			
	Main Rd	1	122.50	6.25	0.20	153.13			
	Singapura Layout								
	1st Cross Rd	1	70.80	0.75	0.20	10.62			
	2nd Cross Rd	1	121.30	1.15	0.20	27.90			
	3rd Cross Rd	1	185.60	1.45	0.20	53.82			
	4th Cross Rd	1	211.00	1.10	0.20	46.42			
	5th Cross Rd	1	229.50	1.00	0.20	45.90			
	6th Cross Rd From End	1	266.10	1.05	0.20	55.88			
	Cross Rd-1	1	34.70	1.10	0.20	7.63			

Sl No	Description of work	No	Length m	Breadth m	Depth m	Quantity	Unit	Rate in Rs	Amount in Rs
	5th A Cross Rd	1	96.00	0.80	0.20	15.36			
	Patanjali Shop Rd	1	141.40	1.10	0.20	31.11			
	Cross Rd-6	1	20.50	0.80	0.20	3.28			
	Cross Rd-5	1	16.00	0.85	0.20	2.72			
	Cross Rd-4	1	22.20	0.75	0.20	3.33			
	Cross Rd-3	1	24.20	0.90	0.20	4.36			
	Cross Rd-2	1	22.00	0.95	0.20	4.18			
	Cross Rd-1	1	22.70	0.90	0.20	4.09			
	3rd Main Rd	1	178.00	0.95	0.20	33.82			
	2nd Main Rd	1	395.30	0.85	0.20	67.20			
	Cross Rd-7	1	27.30	0.80	0.20	4.37			
	1st Main Rd from end	1	438.00	0.95	0.20	83.22			
	Cross Rd-8	1	27.50	0.80	0.20	4.40			
	Cross Rd-9	1	27.00	0.85	0.20	4.59			
	Kamaru House Rd	1	291.50	1.25	0.20	72.88			
	Muniswamappa Garden								
	6th Main Rd	1	208.00	1.15	0.20	47.84			
	1st Main Rd	1	112.00	1.30	0.20	29.12			
	Cross Rd-1	1	35.30	0.90	0.20	6.61			
	Cross Rd-2	1	50.00	0.80	0.20	8.00			
	Cross Rd-3	1	37.00	0.90	0.20	6.66			
	Cross Rd-4	1	51.40	0.90	0.20	9.25			
	Cross Rd-5	1	53.00	1.00	0.20	10.60			
	Cross Rd-6	1	81.70	1.00	0.20	16.34			
	Cross Rd-7	1	42.70	1.00	0.20	8.54			
	Acchi Store Rd	1	138.60	0.95	0.20	26.33			
	Kuvempu Nagara 2nd Stage								
	Thetar Gate Opposite Rd	1	73.50	1.00	0.20	14.70			
	Varadharaju Nagara								
	1st Cross Rd Left Side	1	61.00	0.90	0.20	10.98			
	1st Cross Rd Right Side	1	35.50	1.00	0.20	7.10			
	2nd Cross Rd Left Side	1	63.60	0.85	0.20	10.81			
	2nd Cross Rd Right Side	1	22.60	0.95	0.20	4.29			
	3rd Cross Rd Left Side	1	66.00	1.00	0.20	13.20			
	3rd Cross Rd Right Side	1	21.00	1.00	0.20	4.20			
	4th Cross Rd Left Side	1	65.50	0.90	0.20	11.79			
	6th A Cross Rd	1	78.00	4.15	0.20	64.74			
	4th A Cross Rd	1	81.00	5.50	0.20	89.10			
	3rd A Cross Rd	1	82.80	5.50	0.20	91.08			
	2nd A Cross Rd	1	84.00	5.25	0.20	88.20			
	1st A Cross Rd	1	71.00	4.95	0.20	70.29			
	5th Cross Rd Right Side	1	237.00	4.50	0.20	213.30			
	1st Cross A Cross Rd	1	18.00	5.25	0.20	18.90			
	Axis Bank Opposite Rd	1	152.50	4.95	0.20	150.98			
	Singapura Garden								
	4th D Cross Rd	1	119.70	1.00	0.20	23.94			
	Vasbalanagara								
	5th Cross Rd	1	144.00	1.15	0.20	33.12			
	Thirumala Store Rd	1	86.00	4.90	0.20	84.28			
	3rd Main 5th Cross Rd	1	537.50	1.85	0.20	198.88			

Sl No	Description of work	No	Length m	Breadth m	Depth m	Quantity	Unit	Rate in Rs	Amount in Rs
	Cross Rd	1	194.50	1.75	0.20	68.08			
	CC Road								
	Ramchandrapura								
	Devappa Layout								
	Main Rd	1	178.10	3.80	0.20	135.36			
	2nd Cross Rd	1	126.40	3.90	0.20	98.59			
	1st Cross Rd	1	116.90	3.95	0.20	92.35			
	Adishakthi Temple Rd	1	101.00	5.40	0.20	109.08			
	Munwshwara Temple Rd	1	63.00	3.60	0.20	45.36			
	Veckavathi House Rd	1	193.30	4.25	0.20	164.31			
	Nirmala House Rd	1	57.90	4.15	0.20	48.06			
	Antonys House Rd	1	58.00	3.95	0.20	45.82			
	Gangamma Temple Rd From en	1	244.50	3.50	0.20	172.52			
	Mariyamma Block								
	Main Rd	1	171.70	5.15	0.20	176.85			
	Kuvempu Nagara 2nd Stage								
	M R Seetham Rao Rd 2nd Cross	1	74.00	5.55	0.20	82.14			
	Naranappa Layout								
	Aniketan House Rd	1	123.60	5.60	0.20	165.27			
	Mukundha House Rd From end	1	82.40	4.85	0.20	79.93			
	Cross Rd-1	1	27.20	4.80	0.20	26.11			
	Cross Rd-2	1	68.20	5.20	0.20	70.93			
	Prakruthi Layout								
	2nd Cross Rd	1	42.30	5.50	0.20	46.53			
	Varadharaju Nagara								
	5th A Cross Rd	1	55.00	5.70	0.20	62.70			
	Cross Rd	1	16.70	4.85	0.20	16.20			
	Pot Holes								
		50	5.00	6.00	0.30	450.00			
		32	1.98	3.00	0.30	57.02			
		50	4.00	3.00	0.30	180.00			
		10	2.00	2.00	0.30	12.00			
		50	4.00	4.00	0.30	240.00			
						5762.32			
					Upto 125%	**2431.16**	**Cum**	**521.96**	**1268969.58**
					Above 125%	**3331.16**	**Cum**	**521.96**	**1738732.94**
	Approved Amount	**521.96**							
11	Loading and Unloading of Stone Boulder/Stone aggregates/ Sand/Kankar/Moorum.(Tipper 5.5 m3)								
	Qty from Item No-2					4644.55			
	Qty from Item No -10					5762.32			
						10406.87	**Cum**	**180.61**	**1879585.50**
	Approved Amount	**180.61**							
12	Wet Mix Macadam (Plant mix method) Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver/grader in sub-base / base course on well prepared surface and compacting with vibratory								
	Asphalt Road								
	Edge Correction/Cut Portion								
	Singapura Paradies								

Sl No	Description of work	No	Length m	Breadth m	Depth m	Quantity	Unit	Rate in Rs	Amount in Rs
	Singapura Paradies								
	6th Main Rd	1	146.50	0.95	0.23	32.01			
	5th Main Rd	1	137.10	0.90	0.23	28.38			
	4th Min Rd	1	147.00	1.00	0.23	33.81			
	2nd Main Rd	1	161.00	1.00	0.23	37.03			
	1st Main Rd	1	165.00	1.15	0.23	43.64			
	1st Main 1st Cross Rd	1	110.50	1.10	0.23	27.96			
	1st Main 2nd Cross Rd	1	108.90	1.15	0.23	28.80			
	1st Main 3rd Cross Rd	1	125.30	1.05	0.23	30.26			
	New Sai Garden								
	4th Cross Rd	1	58.00	6.00	0.23	80.04			
	Ganesh Layout								
	3rd Cross Rd	1	120.40	2.00	0.23	55.38			
	4th Cross Rd	1	115.50	1.05	0.23	27.89			
	Main Rd	1	336.50	1.00	0.23	77.40			
	7th Main Rd	1	55.40	0.70	0.23	8.92			
	6th Main Rd Right Side Rd	1	46.20	0.70	0.23	7.44			
	6th Main Rd Left Side Rd	1	47.00	0.80	0.23	8.65			
	5th Main Rd Left Side Rd	1	36.30	0.80	0.23	6.68			
	5th Main Rd Right Side Rd	1	47.50	0.80	0.23	8.74			
	4th Main Rd Right Side Rd	1	48.90	0.70	0.23	7.87			
	2nd Main Rd Right Side Rd	1	48.90	0.80	0.23	9.00			
	Sri Balaji Layout (Singapura Bus Stop)								
	2nd Cross Rd	1	89.30	6.15	0.23	126.31			
	3rd Cross Rd Left Side Rd	1	76.60	6.50	0.23	114.52			
	3rd Cross Rd Right Side Rd	1	75.00	6.30	0.23	108.68			
	4th Cross Rd Right Side Rd	1	24.50	6.00	0.23	33.81			
	4th Cross Rd Left Side Rd	1	63.70	5.30	0.23	77.65			
	Main Rd	1	122.50	6.25	0.23	176.09			
	Singapura Layout								
	1st Cross Rd	1	70.80	0.75	0.23	12.21			
	2nd Cross Rd	1	121.30	1.15	0.23	32.08			
	3rd Cross Rd	1	185.60	1.45	0.23	61.90			
	4th Cross Rd	1	211.00	1.10	0.23	53.38			
	5th Cross Rd	1	229.50	1.00	0.23	52.79			
	6th Cross Rd From End	1	266.10	1.05	0.23	64.26			
	Cross Rd-1	1	34.70	1.10	0.23	8.78			
	5th A Cross Rd	1	96.00	0.80	0.23	17.66			
	Patanjali Shop Rd	1	141.40	1.10	0.23	35.77			
	Cross Rd-6	1	20.50	0.80	0.23	3.77			
	Cross Rd-5	1	16.00	0.85	0.23	3.13			
	Cross Rd-4	1	22.20	0.75	0.23	3.83			
	Cross Rd-3	1	24.20	0.90	0.23	5.01			
	Cross Rd-2	1	22.00	0.95	0.23	4.81			
	Cross Rd-1	1	22.70	0.90	0.23	4.70			
	3rd Main Rd	1	178.00	0.95	0.23	38.89			
	2nd Main Rd	1	395.30	0.85	0.23	77.28			
	Cross Rd-7	1	27.30	0.80	0.23	5.02			
	1st Main Rd from end	1	438.00	0.95	0.23	95.70			
	Cross Rd-8	1	27.50	0.80	0.23	5.06			

Sl No	Description of work	No	Length m	Breadth m	Depth m	Quantity	Unit	Rate in Rs	Amount in Rs
	Cross Rd-9	1	27.00	0.85	0.23	5.28			
	Kamaru House Rd	1	291.50	1.25	0.23	83.81			
	Muniswamappa Garden								
	6th Main Rd	1	208.00	1.15	0.23	55.02			
	1st Main Rd	1	112.00	1.30	0.23	33.49			
	Cross Rd-1	1	35.30	0.90	0.23	7.60			
	Cross Rd-2	1	50.00	0.80	0.23	9.20			
	Cross Rd-3	1	37.00	0.90	0.23	7.66			
	Cross Rd-4	1	51.40	0.90	0.23	10.64			
	Cross Rd-5	1	53.00	1.00	0.23	12.19			
	Cross Rd-6	1	81.70	1.00	0.23	18.79			
	Cross Rd-7	1	42.70	1.00	0.23	9.82			
	Acchi Store Rd	1	138.60	0.95	0.23	30.28			
	Kuvempu Nagara 2nd Stage								
	Thetar Gate Opposite Rd	1	73.50	1.00	0.23	16.91			
	Varadharaju Nagara								
	1st Cross Rd Left Side	1	61.00	0.90	0.23	12.63			
	1st Cross Rd Right Side	1	35.50	1.00	0.23	8.17			
	2nd Cross Rd Left Side	1	63.60	0.85	0.23	12.43			
	2nd Cross Rd Right Side	1	22.60	0.95	0.23	4.94			
	3rd Cross Rd Left Side	1	66.00	1.00	0.23	15.18			
	3rd Cross Rd Right Side	1	21.00	1.00	0.23	4.83			
	4th Cross Rd Left Side	1	65.50	0.90	0.23	13.56			
	6th A Cross Rd	1	78.00	4.15	0.23	74.45			
	4th A Cross Rd	1	81.00	5.50	0.23	102.47			
	3rd A Cross Rd	1	82.80	5.50	0.23	104.74			
	2nd A Cross Rd	1	84.00	5.25	0.23	101.43			
	1st A Cross Rd	1	71.00	4.95	0.23	80.83			
	5th Cross Rd Right Side	1	237.00	4.50	0.23	245.30			
	1st Cross A Cross Rd	1	18.00	5.25	0.23	21.74			
	Axis Bank Opposite Rd	1	152.50	4.95	0.23	173.62			
	Singapura Garden								
	4th D Cross Rd	1	119.70	1.00	0.23	27.53			
	Vasbalanagara								
	5th Cross Rd	1	144.00	1.15	0.23	38.09			
	Thirumala Store Rd	1	86.00	4.90	0.23	96.92			
	3rd Main 5th Cross Rd	1	537.50	1.85	0.23	268.76			
	Cross Rd	1	194.50	1.75	0.23	78.29			
	Sri Balaji Layout (Singapura Bus Stop)								
	Main Rd	1	81.30	5.95	0.23	111.26			
	Pot Holes								
		50	5.00	6.00	0.23	345.00			
		32	1.98	3.00	0.23	43.72			
		50	4.00	3.00	0.23	138.00			
		10	2.00	2.00	0.23	9.20			
		50	4.00	4.00	0.23	184.00			
						4400.75	**Cum**		
					Upto 125%	**2110.80**	**Cum**	**2764.54**	**5835391.03**
					Above 125%	**2289.95**	**Cum**	**2764.54**	**6330669.13**
	Approved Amount	**2764.54**							

Sl No	Description of work	No	Length m	Breadth m	Depth m	Quantity	Unit	Rate in Rs	Amount in Rs
13	Providing and applying primer coat with SS1 grade Bitumen Emulsion on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.90 kg per m2 using mechanical means. Prime Coat over WMM/WBM								
	Asphalt Road								
	Edge Correction/Cut Portion								
	Singapura Paradies								
	Singapura Paradies								
	6th Main Rd	1	146.50	0.95		139.18			
	5th Main Rd	1	137.10	0.90		123.39			
	4th Min Rd	1	147.00	1.00		147.00			
	2nd Main Rd	1	161.00	1.00		161.00			
	1st Main Rd	1	165.00	1.15		189.75			
	1st Main 1st Cross Rd	1	110.50	1.10		121.55			
	1st Main 2nd Cross Rd	1	108.90	1.15		125.24			
	1st Main 3rd Cross Rd	1	125.30	1.05		131.57			
	New Sai Garden								
	4th Cross Rd	1	58.00	6.00		348.00			
	3rd Cross Rd	1	54.30	5.70		309.51			
	2nd Cross Rd	1	47.50	5.70		270.75			
	Ganesh Layout								
	3rd Cross Rd	1	120.40	2.00		240.80			
	4th Cross Rd	1	115.50	1.05		121.28			
	Main Rd	1	336.50	1.00		336.50			
	7th Main Rd	1	55.40	0.70		38.78			
	6th Main Rd Right Side Rd	1	46.20	0.70		32.34			
	6th Main Rd Left Side Rd	1	47.00	0.80		37.60			
	5th Main Rd Left Side Rd	1	36.30	0.80		29.04			
	5th Main Rd Right Side Rd	1	47.50	0.80		38.00			
	4th Main Rd Right Side Rd	1	48.90	0.70		34.23			
	2nd Main Rd Right Side Rd	1	48.90	0.80		39.12			
	Sri Balaji Layout (Singapura Bus Stop)								
	2nd Cross Rd	1	89.30	6.15		549.20			
	3rd Cross Rd Left Side Rd	1	76.60	6.50		497.90			
	3rd Cross Rd Right Side Rd	1	75.00	6.30		472.50			
	4th Cross Rd Right Side Rd	1	24.50	6.00		147.00			
	4th Cross Rd Left Side Rd	1	63.70	5.30		337.61			
	Main Rd	1	122.50	6.25		765.63			
	Singapura Layout								
	1st Cross Rd	1	70.80	0.75		53.10			
	2nd Cross Rd	1	121.30	1.15		139.50			
	3rd Cross Rd	1	185.60	1.45		269.12			
	4th Cross Rd	1	211.00	1.10		232.10			
	5th Cross Rd	1	229.50	1.00		229.50			
	6th Cross Rd From End	1	266.10	1.05		279.41			
	Cross Rd-1	1	34.70	1.10		38.17			
	5th A Cross Rd	1	96.00	0.80		76.80			
	Patanjali Shop Rd	1	141.40	1.10		155.54			
	Cross Rd-6	1	20.50	0.80		16.40			
	Cross Rd-5	1	16.00	0.85		13.60			
	Cross Rd-4	1	22.20	0.75		16.65			

Sl No	Description of work	No	Length m	Breadth m	Depth m	Quantity	Unit	Rate in Rs	Amount in Rs
	Cross Rd-3	1	24.20	0.90		21.78			
	Cross Rd-2	1	22.00	0.95		20.90			
	Cross Rd-1	1	22.70	0.90		20.43			
	3rd Main Rd	1	178.00	0.95		169.10			
	2nd Main Rd	1	395.30	0.85		336.01			
	Cross Rd-7	1	27.30	0.80		21.84			
	1st Main Rd from end	1	438.00	0.95		416.10			
	Cross Rd-8	1	27.50	0.80		22.00			
	Cross Rd-9	1	27.00	0.85		22.95			
	Kamaru House Rd	1	291.50	1.25		364.38			
	Muniswamappa Garden								
	6th Main Rd	1	208.00	1.15		239.20			
	1st Main Rd	1	112.00	1.30		145.60			
	Cross Rd-1	1	35.30	0.90		31.77			
	Cross Rd-2	1	50.00	0.80		40.00			
	Cross Rd-3	1	37.00	0.90		33.30			
	Cross Rd-4	1	51.40	0.90		46.26			
	Cross Rd-5	1	53.00	1.00		53.00			
	Cross Rd-6	1	81.70	1.00		81.70			
	Cross Rd-7	1	42.70	1.00		42.70			
	Acchi Store Rd	1	138.60	0.95		131.67			
	Kuvempu Nagara 2nd Stage								
	Thetar Gate Opposite Rd	1	73.50	1.00		73.50			
	Varadharaju Nagara								
	1st Cross Rd Left Side	1	61.00	0.90		54.90			
	1st Cross Rd Right Side	1	35.50	1.00		35.50			
	2nd Cross Rd Left Side	1	63.60	0.85		54.06			
	2nd Cross Rd Right Side	1	22.60	0.95		21.47			
	3rd Cross Rd Left Side	1	66.00	1.00		66.00			
	3rd Cross Rd Right Side	1	21.00	1.00		21.00			
	4th Cross Rd Left Side	1	65.50	0.90		58.95			
	6th A Cross Rd	1	78.00	4.15		323.70			
	4th A Cross Rd	1	81.00	5.50		445.50			
	3rd A Cross Rd	1	82.80	5.50		455.40			
	2nd A Cross Rd	1	84.00	5.25		441.00			
	1st A Cross Rd	1	71.00	4.95		351.45			
	5th Cross Rd Right Side	1	237.00	4.50		1066.50			
	1st Cross A Cross Rd	1	18.00	5.25		94.50			
	Axis Bank Opposite Rd	1	152.50	4.95		754.88			
	Singapura Garden								
	4th D Cross Rd	1	119.70	1.00		119.70			
	Vasbalanagara								
	5th Cross Rd	1	144.00	1.15		165.60			
	Thirumala Store Rd	1	86.00	4.90		421.40			
	3rd Main 5th Cross Rd	1	537.50	1.85		994.38			
	Cross Rd	1	194.50	1.75		341.79			
	Pot Holes								
		50	5.00	6.00		1500.00			
		32	1.98	3.00		190.08			
		50	4.00	3.00		600.00			

Sl No	Description of work	No	Length m	Breadth m	Depth m	Quantity	Unit	Rate in Rs	Amount in Rs
		10	2.00	2.00		40.00			
		50	4.00	4.00		800.00			
						19056.25	**Sqm**		
					Upto 125%	**10554.03**	**Sqm**	**48.50**	**511870.21**
					Above 125%	**8502.22**	**Sqm**	**48.50**	**412357.79**
	Approved Amount		**48.50**						
14	Tack coat on Bituminous surface Providing and applying tack coat with VG - 10 Bitumen using pressure distributor at the rate of 0.20 kg/sqm on the prepared bituminous surface cleaned with mechanical broom								
	Asphalt Road								
	Edge Correction/Cut Portion								
	For DBM								
	Singapura Paradies								
	6th Main Rd	1	146.50	0.95		139.18			
	5th Main Rd	1	137.10	0.90		123.39			
	4th Min Rd	1	147.00	1.00		147.00			
	2nd Main Rd	1	161.00	1.00		161.00			
	1st Main Rd	1	165.00	1.15		189.75			
	1st Main 1st Cross Rd	1	110.50	1.10		121.55			
	1st Main 2nd Cross Rd	1	108.90	1.15		125.24			
	1st Main 3rd Cross Rd	1	125.30	1.05		131.57			
	New Sai Garden								
	4th Cross Rd	1	58.00	6.00		348.00			
	3rd Cross Rd	1	54.30	5.70		309.51			
	2nd Cross Rd	1	47.50	5.70		270.75			
	Ganesh Layout								
	3rd Cross Rd	1	120.40	2.00		240.80			
	4th Cross Rd	1	115.50	1.05		121.28			
	Main Rd	1	336.50	1.00		336.50			
	7th Main Rd	1	55.40	0.70		38.78			
	6th Main Rd Right Side Rd	1	46.20	0.70		32.34			
	6th Main Rd Left Side Rd	1	47.00	0.80		37.60			
	5th Main Rd Left Side Rd	1	36.30	0.80		29.04			
	5th Main Rd Right Side Rd	1	47.50	0.80		38.00			
	4th Main Rd Right Side Rd	1	48.90	0.70		34.23			
	2nd Main Rd Right Side Rd	1	48.90	0.80		39.12			
	Sri Balaji Layout (Singapura Bus Stop)								
	2nd Cross Rd	1	89.30	6.15		549.20			
	3rd Cross Rd Left Side Rd	1	76.60	6.50		497.90			
	3rd Cross Rd Right Side Rd	1	75.00	6.30		472.50			
	4th Cross Rd Right Side Rd	1	24.50	6.00		147.00			
	4th Cross Rd Left Side Rd	1	63.70	5.30		337.61			
	Main Rd	1	122.50	6.25		765.63			
	Singapura Layout								
	1st Cross Rd	1	70.80	0.75		53.10			
	2nd Cross Rd	1	121.30	1.15		139.50			
	3rd Cross Rd	1	185.60	1.45		269.12			
	4th Cross Rd	1	211.00	1.10		232.10			

Sl No	Description of work	No	Length m	Breadth m	Depth m	Quantity	Unit	Rate in Rs	Amount in Rs
	5th Cross Rd	1	229.50	1.00		229.50			
	6th Cross Rd From End	1	266.10	1.05		279.41			
	Cross Rd-1	1	34.70	1.10		38.17			
	5th A Cross Rd	1	96.00	0.80		76.80			
	Patanjali Shop Rd	1	141.40	1.10		155.54			
	Cross Rd-6	1	20.50	0.80		16.40			
	Cross Rd-5	1	16.00	0.85		13.60			
	Cross Rd-4	1	22.20	0.75		16.65			
	Cross Rd-3	1	24.20	0.90		21.78			
	Cross Rd-2	1	22.00	0.95		20.90			
	Cross Rd-1	1	22.70	0.90		20.43			
	3rd Main Rd	1	178.00	0.95		169.10			
	2nd Main Rd	1	395.30	0.85		336.01			
	Cross Rd-7	1	27.30	0.80		21.84			
	1st Main Rd from end	1	438.00	0.95		416.10			
	Cross Rd-8	1	27.50	0.80		22.00			
	Cross Rd-9	1	27.00	0.85		22.95			
	Kamaru House Rd	1	291.50	1.25		364.38			
	Muniswamappa Garden								
	6th Main Rd	1	208.00	1.15		239.20			
	1st Main Rd	1	112.00	1.30		145.60			
	Cross Rd-1	1	35.30	0.90		31.77			
	Cross Rd-2	1	50.00	0.80		40.00			
	Cross Rd-3	1	37.00	0.90		33.30			
	Cross Rd-4	1	51.40	0.90		46.26			
	Cross Rd-5	1	53.00	1.00		53.00			
	Cross Rd-6	1	81.70	1.00		81.70			
	Cross Rd-7	1	42.70	1.00		42.70			
	Acchi Store Rd	1	138.60	0.95		131.67			
	Kuvempu Nagara 2nd Stage								
	Thetar Gate Opposite Rd	1	73.50	1.00		73.50			
	Varadharaju Nagara								
	1st Cross Rd Left Side	1	61.00	0.90		54.90			
	1st Cross Rd Right Side	1	35.50	1.00		35.50			
	2nd Cross Rd Left Side	1	63.60	0.85		54.06			
	2nd Cross Rd Right Side	1	22.60	0.95		21.47			
	3rd Cross Rd Left Side	1	66.00	1.00		66.00			
	3rd Cross Rd Right Side	1	21.00	1.00		21.00			
	4th Cross Rd Left Side	1	65.50	0.90		58.95			
	6th A Cross Rd	1	78.00	4.15		323.70			
	4th A Cross Rd	1	81.00	5.50		445.50			
	3rd A Cross Rd	1	82.80	5.50		455.40			
	2nd A Cross Rd	1	84.00	5.25		441.00			
	1st A Cross Rd	1	71.00	4.95		351.45			
	5th Cross Rd Right Side	1	237.00	4.50		1066.50			
	1st Cross A Cross Rd	1	18.00	5.25		94.50			
	Axis Bank Opposite Rd	1	152.50	4.95		754.88			
	Singapura Garden								
	4th D Cross Rd	1	119.70	1.00		119.70			
	Vasbalanagara								

Sl No	Description of work	No	Length m	Breadth m	Depth m	Quantity	Unit	Rate in Rs	Amount in Rs
	5th Cross Rd	1	144.00	1.15		165.60			
	Thirumala Store Rd	1	86.00	4.90		421.40			
	3rd Main 5th Cross Rd	1	537.50	1.85		994.38			
	Cross Rd	1	194.50	1.75		341.79			
	For BC								
	Singapura Paradies								
	6th Main Rd	1	146.50	4.50		659.25			
	5th Main Rd	1	137.10	4.80		658.08			
	4th Min Rd	1	147.00	4.50		661.50			
	2nd Main Rd	1	161.00	5.50		885.50			
	1st Main Rd	1	165.00	6.60		1089.00			
	1st Main 1st Cross Rd	1	110.50	4.50		497.25			
	1st Main 2nd Cross Rd	1	108.90	4.60		500.94			
	1st Main 3rd Cross Rd	1	125.30	5.10		639.03			
	New Sai Garden								
	4th Cross Rd	1	58.00	6.00		348.00			
	3rd Cross Rd	1	54.30	5.70		309.51			
	2nd Cross Rd	1	47.50	5.70		270.75			
	Ganesh Layout								
	3rd Cross Rd	1	120.40	5.65		680.26			
	4th Cross Rd	1	115.50	5.45		629.48			
	Main Rd	1	336.50	5.00		1682.50			
	7th Main Rd	1	55.40	3.70		204.98			
	6th Main Rd Right Side Rd	1	46.20	3.90		180.18			
	6th Main Rd Left Side Rd	1	47.00	3.65		171.55			
	5th Main Rd Left Side Rd	1	36.30	3.30		119.79			
	5th Main Rd Right Side Rd	1	47.50	3.70		175.75			
	4th Main Rd Right Side Rd	1	48.90	3.50		171.15			
	2nd Main Rd Right Side Rd	1	48.90	4.35		212.72			
	Sri Balaji Layout (Singapura Bus Stop)								
	2nd Cross Rd	1	89.30	6.15		549.20			
	3rd Cross Rd Left Side Rd	1	76.60	6.50		497.90			
	3rd Cross Rd Right Side Rd	1	75.00	6.30		472.50			
	4th Cross Rd Right Side Rd	1	24.50	6.00		147.00			
	4th Cross Rd Left Side Rd	1	63.70	5.30		337.61			
	Main Rd	1	122.50	6.25		765.63			
	Singapura Layout								
	1st Cross Rd	1	70.80	3.80		269.04			
	2nd Cross Rd	1	121.30	5.20		630.76			
	3rd Cross Rd	1	185.60	4.90		909.44			
	4th Cross Rd	1	211.00	4.70		991.70			
	5th Cross Rd	1	229.50	4.20		963.90			
	6th Cross Rd From End	1	266.10	5.00		1330.50			
	Cross Rd-1	1	34.70	4.85		168.30			
	5th A Cross Rd	1	96.00	3.80		364.80			
	Patanjali Shop Rd	1	141.40	5.20		735.28			
	Cross Rd-6	1	20.50	4.00		82.00			
	Cross Rd-5	1	16.00	4.40		70.40			
	Cross Rd-4	1	22.20	3.80		84.36			
	Cross Rd-3	1	24.20	3.55		85.91			

Sl No	Description of work	No	Length m	Breadth m	Depth m	Quantity	Unit	Rate in Rs	Amount in Rs
	Cross Rd-2	1	22.00	4.10		90.20			
	Cross Rd-1	1	22.70	3.40		77.18			
	3rd Main Rd	1	178.00	4.00		712.00			
	2nd Main Rd	1	395.30	4.20		1660.26			
	Cross Rd-7	1	27.30	3.60		98.28			
	1st Main Rd from end	1	438.00	4.30		1883.40			
	Cross Rd-8	1	27.50	3.90		107.25			
	Cross Rd-9	1	27.00	3.20		86.40			
	Kamaru House Rd	1	291.50	4.60		1340.90			
	Muniswamappa Garden								
	6th Main Rd	1	208.00	5.00		1040.00			
	1st Main Rd	1	112.00	6.30		705.60			
	Cross Rd-1	1	35.30	3.80		134.14			
	Cross Rd-2	1	50.00	4.30		215.00			
	Cross Rd-3	1	37.00	3.70		136.90			
	Cross Rd-4	1	51.40	3.70		190.18			
	Cross Rd-5	1	53.00	4.00		212.00			
	Cross Rd-6	1	81.70	4.10		334.97			
	Cross Rd-7	1	42.70	4.70		200.69			
	Acchi Store Rd	1	138.60	4.25		589.05			
	Kuvempu Nagara 2nd Stage								
	Thetar Gate Opposite Rd	1	73.50	4.50		330.75			
	Varadharaju Nagara								
	1st Cross Rd Left Side	1	61.00	4.95		301.95			
	1st Cross Rd Right Side	1	35.50	5.10		181.05			
	2nd Cross Rd Left Side	1	63.60	4.70		298.92			
	2nd Cross Rd Right Side	1	22.60	4.30		97.18			
	3rd Cross Rd Left Side	1	66.00	4.70		310.20			
	3rd Cross Rd Right Side	1	21.00	4.90		102.90			
	4th Cross Rd Left Side	1	65.50	4.10		268.55			
	6th A Cross Rd	1	78.00	4.15		323.70			
	4th A Cross Rd	1	81.00	5.50		445.50			
	3rd A Cross Rd	1	82.80	5.50		455.40			
	2nd A Cross Rd	1	84.00	5.25		441.00			
	1st A Cross Rd	1	71.00	4.95		351.45			
	5th Cross Rd Right Side	1	237.00	4.50		1066.50			
	1st Cross A Cross Rd	1	18.00	5.25		94.50			
	Axis Bank Opposite Rd	1	152.50	4.95		754.88			
	Singapura Garden								
	4th D Cross Rd	1	119.70	5.00		598.50			
	Vasbalanagara								
	5th Cross Rd	1	144.00	5.85		842.40			
	Thirumala Store Rd	1	86.00	4.90		421.40			
	3rd Main 5th Cross Rd	1	537.50	6.25		3644.92			
	Cross Rd	1	194.50	6.80		1349.32			
	Pot Holes								
		50	5.00	6.00		1500.00			
		32	1.98	3.00		190.08			
		50	4.00	3.00		600.00			
		10	2.00	2.00		40.00			

Sl No	Description of work	No	Length m	Breadth m	Depth m	Quantity	Unit	Rate in Rs	Amount in Rs
		50	4.00	4.00		800.00			
						61754.99	**Nos**	**13.86**	**855924.11**
	Approved Amount		**13.86**						
15	Providing and laying Dense Graded Bituminous Macadam with 40/60 TPH capacity HMP using crushed aggregates ofspecified grading, premixed with bituminous binder VG-40, @ 4.5 per cent by weight of total mix and filler, transporting the hot mix to work site, laying with mechanical paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRTH specification clause No. 505 complete in all respects								
	Asphalt Road								
	Edge Correction/Cut Portion								
	Singapura Paradies								
	6th Main Rd	1	146.50	0.95	0.05	6.96			
	5th Main Rd	1	137.10	0.90	0.05	6.17			
	4th Min Rd	1	147.00	1.00	0.05	7.35			
	2nd Main Rd	1	161.00	1.00	0.05	8.05			
	1st Main Rd	1	165.00	1.15	0.05	9.49			
	1st Main 1st Cross Rd	1	110.50	1.10	0.05	6.08			
	1st Main 2nd Cross Rd	1	108.90	1.15	0.05	6.26			
	1st Main 3rd Cross Rd	1	125.30	1.05	0.05	6.58			
	New Sai Garden								
	4th Cross Rd	1	58.00	6.00	0.05	17.40			
	3rd Cross Rd	1	54.30	5.70	0.05	15.48			
	2nd Cross Rd	1	47.50	5.70	0.05	13.54			
	Ganesh Layout								
	3rd Cross Rd	1	120.40	2.00	0.05	12.04			
	4th Cross Rd	1	115.50	1.05	0.05	6.06			
	Main Rd	1	336.50	1.00	0.05	16.83			
	7th Main Rd	1	55.40	0.70	0.05	1.94			
	6th Main Rd Right Side Rd	1	46.20	0.70	0.05	1.62			
	6th Main Rd Left Side Rd	1	47.00	0.80	0.05	1.88			
	5th Main Rd Left Side Rd	1	36.30	0.80	0.05	1.45			
	5th Main Rd Right Side Rd	1	47.50	0.80	0.05	1.90			
	4th Main Rd Right Side Rd	1	48.90	0.70	0.05	1.71			
	2nd Main Rd Right Side Rd	1	48.90	0.80	0.05	1.96			
	Sri Balaji Layout (Singapura Bus Stop)								
	2nd Cross Rd	1	89.30	6.15	0.05	27.46			
	3rd Cross Rd Left Side Rd	1	76.60	6.50	0.05	24.90			
	3rd Cross Rd Right Side Rd	1	75.00	6.30	0.05	23.63			
	4th Cross Rd Right Side Rd	1	24.50	6.00	0.05	7.35			
	4th Cross Rd Left Side Rd	1	63.70	5.30	0.05	16.88			
	Main Rd	1	122.50	6.25	0.05	38.28			
	Singapura Layout								
	1st Cross Rd	1	70.80	0.75	0.05	2.66			
	2nd Cross Rd	1	121.30	1.15	0.05	6.97			
	3rd Cross Rd	1	185.60	1.45	0.05	13.46			
	4th Cross Rd	1	211.00	1.10	0.05	11.61			
	5th Cross Rd	1	229.50	1.00	0.05	11.48			
	6th Cross Rd From End	1	266.10	1.05	0.05	13.97			
	Cross Rd-1	1	34.70	1.10	0.05	1.91			

Sl No	Description of work	No	Length m	Breadth m	Depth m	Quantity	Unit	Rate in Rs	Amount in Rs
	5th A Cross Rd	1	96.00	0.80	0.05	3.84			
	Patanjali Shop Rd	1	141.40	1.10	0.05	7.78			
	Cross Rd-6	1	20.50	0.80	0.05	0.82			
	Cross Rd-5	1	16.00	0.85	0.05	0.68			
	Cross Rd-4	1	22.20	0.75	0.05	0.83			
	Cross Rd-3	1	24.20	0.90	0.05	1.09			
	Cross Rd-2	1	22.00	0.95	0.05	1.05			
	Cross Rd-1	1	22.70	0.90	0.05	1.02			
	3rd Main Rd	1	178.00	0.95	0.05	8.46			
	2nd Main Rd	1	395.30	0.85	0.05	16.80			
	Cross Rd-7	1	27.30	0.80	0.05	1.09			
	1st Main Rd from end	1	438.00	0.95	0.05	20.81			
	Cross Rd-8	1	27.50	0.80	0.05	1.10			
	Cross Rd-9	1	27.00	0.85	0.05	1.15			
	Kamaru House Rd	1	291.50	1.25	0.05	18.22			
	Muniswamappa Garden								
	6th Main Rd	1	208.00	1.15	0.05	11.96			
	1st Main Rd	1	112.00	1.30	0.05	7.28			
	Cross Rd-1	1	35.30	0.90	0.05	1.59			
	Cross Rd-2	1	50.00	0.80	0.05	2.00			
	Cross Rd-3	1	37.00	0.90	0.05	1.67			
	Cross Rd-4	1	51.40	0.90	0.05	2.31			
	Cross Rd-5	1	53.00	1.00	0.05	2.65			
	Cross Rd-6	1	81.70	1.00	0.05	4.09			
	Cross Rd-7	1	42.70	1.00	0.05	2.14			
	Acchi Store Rd	1	138.60	0.95	0.05	6.58			
	Kuvempu Nagara 2nd Stage								
	Thetar Gate Opposite Rd	1	73.50	1.00	0.05	3.68			
	Varadharaju Nagara								
	1st Cross Rd Left Side	1	61.00	0.90	0.05	2.75			
	1st Cross Rd Right Side	1	35.50	1.00	0.05	1.78			
	2nd Cross Rd Left Side	1	63.60	0.85	0.05	2.70			
	2nd Cross Rd Right Side	1	22.60	0.95	0.05	1.07			
	3rd Cross Rd Left Side	1	66.00	1.00	0.05	3.30			
	3rd Cross Rd Right Side	1	21.00	1.00	0.05	1.05			
	4th Cross Rd Left Side	1	65.50	0.90	0.05	2.95			
	6th A Cross Rd	1	78.00	4.15	0.05	16.19			
	4th A Cross Rd	1	81.00	5.50	0.05	22.28			
	3rd A Cross Rd	1	82.80	5.50	0.05	22.77			
	2nd A Cross Rd	1	84.00	5.25	0.05	22.05			
	1st A Cross Rd	1	71.00	4.95	0.05	17.57			
	5th Cross Rd Right Side	1	237.00	4.50	0.05	53.33			
	1st Cross A Cross Rd	1	18.00	5.25	0.05	4.73			
	Axis Bank Opposite Rd	1	152.50	4.95	0.05	37.74			
	Singapura Garden								
	4th D Cross Rd	1	119.70	1.00	0.05	5.99			
	Vasbalanagara								
	5th Cross Rd	1	144.00	1.15	0.05	8.28			
	Thirumala Store Rd	1	86.00	4.90	0.05	21.07			
	3rd Main 5th Cross Rd	1	537.50	1.85	0.05	53.94			

Sl No	Description of work	No	Length m	Breadth m	Depth m	Quantity	Unit	Rate in Rs	Amount in Rs
	Cross Rd	1	194.50	1.75	0.05	16.92			
	Pot Holes								
		50	5.00	6.00	0.05	75.00			
		32	1.98	3.00	0.05	9.50			
		50	4.00	3.00	0.05	30.00			
		10	2.00	2.00	0.05	2.00			
		50	4.00	4.00	0.05	40.00			
						956.87	**Cum**	**10859.55**	**10391164.52**
	Approved Amount	**10859.55**							
16	Providing and laying Bituminous Concrete with 40/60 TPH capacity hot mix plant using crushed aggregates of specified grading, premixed with bituminous binder VG-30, @ 5.4 per cent of mix and filler, transporting the hot mix to work site,laying with mechanical paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 507 complete in all respects								
	Asphalt Road								
	Edge Correction/Cut Portion								
	Singapura Paradies								
	6th Main Rd	1	146.50	4.50	0.04	26.37			
	5th Main Rd	1	137.10	4.80	0.04	26.32			
	4th Min Rd	1	147.00	4.50	0.04	26.46			
	2nd Main Rd	1	161.00	5.50	0.04	35.42			
	1st Main Rd	1	165.00	6.60	0.04	43.56			
	1st Main 1st Cross Rd	1	110.50	4.50	0.04	19.89			
	1st Main 2nd Cross Rd	1	108.90	4.60	0.04	20.04			
	1st Main 3rd Cross Rd	1	125.30	5.10	0.04	25.56			
	New Sai Garden								
	4th Cross Rd	1	58.00	6.00	0.04	13.92			
	3rd Cross Rd	1	54.30	5.70	0.04	12.38			
	2nd Cross Rd	1	47.50	5.70	0.04	10.83			
	Ganesh Layout								
	3rd Cross Rd	1	120.40	5.65	0.04	27.21			
	4th Cross Rd	1	115.50	5.45	0.04	25.18			
	Main Rd	1	336.50	5.00	0.04	67.30			
	7th Main Rd	1	55.40	3.70	0.04	8.20			
	6th Main Rd Right Side Rd	1	46.20	3.90	0.04	7.21			
	6th Main Rd Left Side Rd	1	47.00	3.65	0.04	6.86			
	5th Main Rd Left Side Rd	1	36.30	3.30	0.04	4.79			
	5th Main Rd Right Side Rd	1	47.50	3.70	0.04	7.03			
	4th Main Rd Right Side Rd	1	48.90	3.50	0.04	6.85			
	2nd Main Rd Right Side Rd	1	48.90	4.35	0.04	8.51			
	Sri Balaji Layout (Singapura Bus Stop)								
	2nd Cross Rd	1	89.30	6.15	0.04	21.97			
	3rd Cross Rd Left Side Rd	1	76.60	6.50	0.04	19.92			
	3rd Cross Rd Right Side Rd	1	75.00	6.30	0.04	18.90			
	4th Cross Rd Right Side Rd	1	24.50	6.00	0.04	5.88			
	4th Cross Rd Left Side Rd	1	63.70	5.30	0.04	13.50			
	Main Rd	1	122.50	6.25	0.04	30.63			
	Singapura Layout								
	1st Cross Rd	1	70.80	3.80	0.04	10.76			

Sl No	Description of work	No	Length m	Breadth m	Depth m	Quantity	Unit	Rate in Rs	Amount in Rs
	2nd Cross Rd	1	121.30	5.20	0.04	25.23			
	3rd Cross Rd	1	185.60	4.90	0.04	36.38			
	4th Cross Rd	1	211.00	4.70	0.04	39.67			
	5th Cross Rd	1	229.50	4.20	0.04	38.56			
	6th Cross Rd From End	1	266.10	5.00	0.04	53.22			
	Cross Rd-1	1	34.70	4.85	0.04	6.73			
	5th A Cross Rd	1	96.00	3.80	0.04	14.59			
	Patanjali Shop Rd	1	141.40	5.20	0.04	29.41			
	Cross Rd-6	1	20.50	4.00	0.04	3.28			
	Cross Rd-5	1	16.00	4.40	0.04	2.82			
	Cross Rd-4	1	22.20	3.80	0.04	3.37			
	Cross Rd-3	1	24.20	3.55	0.04	3.44			
	Cross Rd-2	1	22.00	4.10	0.04	3.61			
	Cross Rd-1	1	22.70	3.40	0.04	3.09			
	3rd Main Rd	1	178.00	4.00	0.04	28.48			
	2nd Main Rd	1	395.30	4.20	0.04	66.41			
	Cross Rd-7	1	27.30	3.60	0.04	3.93			
	1st Main Rd from end	1	438.00	4.30	0.04	75.34			
	Cross Rd-8	1	27.50	3.90	0.04	4.29			
	Cross Rd-9	1	27.00	3.20	0.04	3.46			
	Kamaru House Rd	1	291.50	4.60	0.04	53.64			
	Muniswamappa Garden								
	6th Main Rd	1	208.00	5.00	0.04	41.60			
	1st Main Rd	1	112.00	6.30	0.04	28.22			
	Cross Rd-1	1	35.30	3.80	0.04	5.37			
	Cross Rd-2	1	50.00	4.30	0.04	8.60			
	Cross Rd-3	1	37.00	3.70	0.04	5.48			
	Cross Rd-4	1	51.40	3.70	0.04	7.61			
	Cross Rd-5	1	53.00	4.00	0.04	8.48			
	Cross Rd-6	1	81.70	4.10	0.04	13.40			
	Cross Rd-7	1	42.70	4.70	0.04	8.03			
	Acchi Store Rd	1	138.60	4.25	0.04	23.56			
	Kuvempu Nagara 2nd Stage								
	Thetar Gate Opposite Rd	1	73.50	4.50	0.04	13.23			
	Varadharaju Nagara								
	1st Cross Rd Left Side	1	61.00	4.95	0.04	12.08			
	1st Cross Rd Right Side	1	35.50	5.10	0.04	7.24			
	2nd Cross Rd Left Side	1	63.60	4.70	0.04	11.96			
	2nd Cross Rd Right Side	1	22.60	4.30	0.04	3.89			
	3rd Cross Rd Left Side	1	66.00	4.70	0.04	12.41			
	3rd Cross Rd Right Side	1	21.00	4.90	0.04	4.12			
	4th Cross Rd Left Side	1	65.50	4.10	0.04	10.74			
	6th A Cross Rd	1	78.00	4.15	0.04	12.95			
	4th A Cross Rd	1	81.00	5.50	0.04	17.82			
	3rd A Cross Rd	1	82.80	5.50	0.04	18.22			
	2nd A Cross Rd	1	84.00	5.25	0.04	17.64			
	1st A Cross Rd	1	71.00	4.95	0.04	14.06			
	5th Cross Rd Right Side	1	237.00	4.50	0.04	42.66			
	1st Cross A Cross Rd	1	18.00	5.25	0.04	3.78			
	Axis Bank Opposite Rd	1	152.50	4.95	0.04	30.20			

Sl No	Description of work	No	Length m	Breadth m	Depth m	Quantity	Unit	Rate in Rs	Amount in Rs
	Singapura Garden								
	4th D Cross Rd	1	119.70	5.00	0.04	23.94			
	Vasbalanagara								
	5th Cross Rd	1	144.00	5.85	0.04	33.70			
	Thirumala Store Rd	1	101.00	4.90	0.04	19.80			
	3rd Main 5th Cross Rd	1	550.00	6.25	0.04	142.44			
	Cross Rd	1	196.00	6.80	0.04	54.39			
						1707.95	**Cum**	**12253.37**	**20928125.40**
	Approved Amount	**12253.37**							
17	Road Marking with Hot Applied Thermoplastic Compound with Re flectorising Glass Beads on Bituminous Surface Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 g/ m2 area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35:2015.The finished surface to be level, uniform and free from streaks and holes								
	Asphalt Road								
	Singapura Paradies								
	6th Main Rd	2	146.50	0.10		29.30			
	5th Main Rd	2	137.10	0.10		27.42			
	4th Min Rd	2	147.00	0.10		29.40			
	2nd Main Rd	2	161.00	0.10		32.20			
	1st Main Rd	2	165.00	0.10		33.00			
	1st Main 1st Cross Rd	2	110.50	0.10		22.10			
	1st Main 2nd Cross Rd	2	108.90	0.10		21.78			
	1st Main 3rd Cross Rd	2	125.30	0.10		25.06			
	New Sai Garden								
	4th Cross Rd	2	58.00	0.10		11.60			
	3rd Cross Rd	2	54.30	0.10		10.86			
	2nd Cross Rd	2	47.50	0.10		9.50			
	Ganesh Layout								
	3rd Cross Rd	2	120.40	0.10		24.08			
	4th Cross Rd	2	115.50	0.10		23.10			
	Main Rd	2	336.50	0.10		67.30			
	7th Main Rd	2	55.40	0.10		11.08			
	6th Main Rd Right Side Rd	2	46.20	0.10		9.24			
	6th Main Rd Left Side Rd	2	47.00	0.10		9.40			
	5th Main Rd Left Side Rd	2	36.30	0.10		7.26			
	5th Main Rd Right Side Rd	2	47.50	0.10		9.50			
	4th Main Rd Right Side Rd	2	48.90	0.10		9.78			
	2nd Main Rd Right Side Rd	2	48.90	0.10		9.78			
	Sri Balaji Layout (Singapura Bus Stop)								
	2nd Cross Rd	2	89.30	0.10		17.86			
	3rd Cross Rd Left Side Rd	2	76.60	0.10		15.32			
	3rd Cross Rd Right Side Rd	2	75.00	0.10		15.00			
	4th Cross Rd Right Side Rd	2	24.50	0.10		4.90			
	4th Cross Rd Left Side Rd	2	63.70	0.10		12.74			
	Main Rd	2	122.50	0.10		24.50			
	Singapura Layout								
	1st Cross Rd	2	70.80	0.10		14.16			
	2nd Cross Rd	2	121.30	0.10		24.26			
	3rd Cross Rd	2	185.60	0.10		37.12			

Sl No	Description of work	No	Length m	Breadth m	Depth m	Quantity	Unit	Rate in Rs	Amount in Rs
	4th Cross Rd	2	211.00	0.10		42.20			
	5th Cross Rd	2	229.50	0.10		45.90			
	6th Cross Rd From End	2	266.10	0.10		53.22			
	Cross Rd-1	2	34.70	0.10		6.94			
	5th A Cross Rd	2	96.00	0.10		19.20			
	Patanjali Shop Rd	2	141.40	0.10		28.28			
	Cross Rd-6	2	20.50	0.10		4.10			
	Cross Rd-5	2	16.00	0.10		3.20			
	Cross Rd-4	2	22.20	0.10		4.44			
	Cross Rd-3	2	24.20	0.10		4.84			
	Cross Rd-2	2	22.00	0.10		4.40			
	Cross Rd-1	2	22.70	0.10		4.54			
	3rd Main Rd	2	178.00	0.10		35.60			
	2nd Main Rd	2	395.30	0.10		79.06			
	Cross Rd-7	2	27.30	0.10		5.46			
	1st Main Rd from end	2	438.00	0.10		87.60			
	Cross Rd-8	2	27.50	0.10		5.50			
	Cross Rd-9	2	27.00	0.10		5.40			
	Kamaru House Rd	2	291.50	0.10		58.30			
	Muniswamappa Garden								
	6th Main Rd	2	208.00	0.10		41.60			
	1st Main Rd	2	112.00	0.10		22.40			
	Cross Rd-1	2	35.30	0.10		7.06			
	Cross Rd-2	2	50.00	0.10		10.00			
	Cross Rd-3	2	37.00	0.10		7.40			
	Cross Rd-4	2	51.40	0.10		10.28			
	Cross Rd-5	2	53.00	0.10		10.60			
	Cross Rd-6	2	81.70	0.10		16.34			
	Cross Rd-7	2	42.70	0.10		8.54			
	Acchi Store Rd	2	138.60	0.10		27.72			
	Kuvempu Nagara 2nd Stage								
	Thetar Gate Opposite Rd	2	73.50	0.10		14.70			
	Varadharaju Nagara								
	1st Cross Rd Left Side	2	61.00	0.10		12.20			
	1st Cross Rd Right Side	2	35.50	0.10		7.10			
	2nd Cross Rd Left Side	2	63.60	0.10		12.72			
	2nd Cross Rd Right Side	2	22.60	0.10		4.52			
	3rd Cross Rd Left Side	2	66.00	0.10		13.20			
	3rd Cross Rd Right Side	2	21.00	0.10		4.20			
	4th Cross Rd Left Side	2	65.50	0.10		13.10			
	6th A Cross Rd	2	78.00	0.10		15.60			
	4th A Cross Rd	2	81.00	0.10		16.20			
	3rd A Cross Rd	2	82.80	0.10		16.56			
	2nd A Cross Rd	2	84.00	0.10		16.80			
	1st A Cross Rd	2	71.00	0.10		14.20			
	5th Cross Rd Right Side	2	237.00	0.10		47.40			
	1st Cross A Cross Rd	2	18.00	0.10		3.60			
	Axis Bank Opposite Rd	2	152.50	0.10		30.50			
	Singapura Garden								
	4th D Cross Rd	2	119.70	0.10		23.94			

Sl No	Description of work	No	Length m	Breadth m	Depth m	Quantity	Unit	Rate in Rs	Amount in Rs
	Vasbalanagara								
	5th Cross Rd	2	144.00	0.10		28.80			
	Thirumala Store Rd	2	86.00	0.10		17.20			
	3rd Main 5th Cross Rd	2	537.50	0.10		108.13			
	Cross Rd	2	194.50	0.10		40.46			
						1719.84	**Sqm**	**551.98**	**949318.49**
	Approved Amount		**551.98**						
18	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately) Mix								
	RCC Drain								
	Shimadri Layout								
	1st Cross Rd	2	101.50	1.10	0.15	33.50			
	2nd Cross Rd	2	65.50	1.00	0.15	19.65			
	3rd Cross Rd	2	107.50	1.00	0.15	32.25			
	4th Cross Rd	2	56.60	1.00	0.15	16.98			
	5th Cross Rd	2	56.20	1.00	0.15	16.94			
	Singapura Paradise								
	6th Main Rd	2	144.80	1.10	0.15	47.78			
	Culvert	2	5.30	1.50	0.15	2.39			
						169.49	**Cum**	**6614.58**	**1121093.92**
	Approved Amount		**6614.58**						
19	Providing and laying in position Reinforced cement concrete for all Foundation works. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticizers laid in finished layers, well compacted using needle vibrators,								
	RCC Drain Raft								
	Shimadri Layout								
	1st Cross Rd	2	101.50	0.90	0.15	27.41			
	2nd Cross Rd	2	65.50	0.75	0.15	14.74			
	3rd Cross Rd	2	107.50	0.75	0.15	24.19			
	4th Cross Rd	2	56.60	0.75	0.15	12.74			
	5th Cross Rd	2	56.20	0.75	0.15	12.97			
	Singapura Paradise								
	6th Main Rd	2	144.80	0.90	0.15	39.10			
	RCC Drain Wall								
	Shimadri Layout								
	1st Cross Rd	4	101.50	0.15	0.60	36.54			
	2nd Cross Rd	4	65.50	0.15	0.60	23.58			
	3rd Cross Rd	4	107.50	0.15	0.60	38.70			
	4th Cross Rd	4	56.60	0.15	0.60	20.38			
	5th Cross Rd	4	56.20	0.15	0.60	20.23			
	Singapura Paradise								
	6th Main Rd	4	144.80	0.15	0.60	52.13			
						322.69			
	Culvert Raft	2	5.30	1.20	0.20	2.54			
	Culvert Wall	4	5.30	0.23	0.45	2.19			
						4.74			

Sl No	Description of work	No	Length m	Breadth m	Depth m	Quantity	Unit	Rate in Rs	Amount in Rs
						327.43	**Cum**	**7206.00**	**2359432.20**
	Approved Amount		**7206.00**						
20	Supplying, Fitting and Placing TMT Fe 500 & above Reinforcement in Foundation / Substructure / Superstructure complete as per Drawing and Technical Specifications								
	Considering steel For Drain @ 60kg / cum	1	322.69	0.06	--	19.70			
	Considering steel For Culvert @ 90 kg / cum	1	4.74	0.09	--	0.43			
						20.13	**Tn**	**97077.74**	**1954295.60**
	Approved Amount		**97077.74**						
21	Dismantling of Cement Concrete Pavement Dismantling of cement concrete pavement by mechanical means using pneumatic tools, breaking to pieces not exceeding 0.02 m3 in volume and stock piling at designated locations and disposal of dismantled materials and stacking serviceable and unserviceable materials separately								
						0.00	**Cum**	**487.32**	**0.00**
	Approved Amount		**487.32**						
22	Dismantling of Flexible pavements and disposal of dismantled materials and stacking serviceable and unserviceable materials separately								
	CC Road								
	Ramchandrapura								
	Devappa Layout								
	Main Rd	1	178.10	3.80	0.10	67.68			
	2nd Cross Rd	1	126.40	3.90	0.10	49.30			
	1st Cross Rd	1	116.90	3.95	0.10	46.18			
	Adishakthi Temple Rd	1	101.00	5.40	0.10	54.54			
	Munwshwara Temple Rd	1	63.00	3.60	0.10	22.68			
	Veckavathi House Rd	1	193.30	4.25	0.10	82.15			
	Nirmala House Rd	1	57.90	4.15	0.10	24.03			
	Antonys House Rd	1	58.00	3.95	0.10	22.91			
	Gangamma Temple Rd From en	1	244.50	3.50	0.10	85.58			
	Mariyamma Block								
	Main Rd	1	171.70	5.15	0.10	96.38			
	Kuvempu Nagara 2nd Stage								
	M R Seetham Rao Rd 2nd Cross	1	74.00	5.55	0.10	48.83			
						600.25	**Cum**	**232.11**	**139324.38**
	Approved Amount		**232.11**						
23	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machinery, curing, and all the other appurtenances required to complete the work as per								
	CC Road								
	CC Road								
	Ramchandrapura								
	Devappa Layout								
	Main Rd	1	178.10	3.80	0.15	101.52			
	2nd Cross Rd	1	126.40	3.90	0.15	73.94			

Sl No	Description of work	No	Length m	Breadth m	Depth m	Quantity	Unit	Rate in Rs	Amount in Rs
	1st Cross Rd	1	116.90	3.95	0.15	69.26			
	Adishakthi Temple Rd	1	101.00	5.40	0.15	81.81			
	Munwshwara Temple Rd	1	63.00	3.60	0.15	34.02			
	Veckavathi House Rd	1	193.30	4.25	0.15	123.23			
	Nirmala House Rd	1	57.90	4.15	0.15	36.04			
	Antonys House Rd	1	58.00	3.95	0.15	34.37			
	Gangamma Temple Rd From en	1	244.50	3.50	0.15	128.36			
	Mariyamma Block								
	Main Rd	1	171.70	5.15	0.15	153.86			
	Kuvempu Nagara 2nd Stage								
	M R Seetham Rao Rd 2nd Cross	1	74.00	5.55	0.15	61.61			
	Naranappa Layout								
	Aniketan House Rd	1	123.60	5.60	0.15	103.82			
	Mukundha House Rd From end	1	82.40	4.85	0.15	59.95			
	Cross Rd-1	1	27.20	4.80	0.15	19.58			
	Cross Rd-2	1	68.20	5.20	0.15	53.20			
	Prakruthi Layout								
	2nd Cross Rd	1	42.30	5.50	0.15	34.90			
	Varadharaju Nagara								
	5th A Cross Rd	1	55.00	5.70	0.15	47.03			
	Cross Rd	1	16.70	4.85	0.15	12.07			
						1228.56	**Cum**	**5611.08**	**6893539.26**
	Approved Amount		**5611.08**						
24	Providing and constructing un-reinforced plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement or any other type as per Clause 1501.2.2 M30 (Grade), coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a concrete mixer of not less than 0.2 cum capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including construction joints, , primer, sealant , curing of concrete slabs for 14- days, and water finishing to lines and grade as per								
	CC Road								
	Ramchandrapura								
	Devappa Layout								
	Main Rd	1	178.10	3.80	0.15	101.52			
	2nd Cross Rd	1	126.40	3.90	0.15	73.94			
	1st Cross Rd	1	116.90	3.95	0.15	69.26			
	Adishakthi Temple Rd	1	101.00	5.40	0.15	81.81			
	Munwshwara Temple Rd	1	63.00	3.60	0.15	34.02			
	Veckavathi House Rd	1	193.30	4.25	0.15	123.23			
	Nirmala House Rd	1	57.90	4.15	0.15	36.04			
	Antonys House Rd	1	58.00	3.95	0.15	34.37			
	Gangamma Temple Rd From en	1	244.50	3.50	0.15	128.36			
	Mariyamma Block								
	Main Rd	1	171.70	5.15	0.15	153.86			
	Kuvempu Nagara 2nd Stage								
	M R Seetham Rao Rd 2nd Cross	1	74.00	5.55	0.15	61.61			
	Naranappa Layout								
	Aniketan House Rd	1	123.60	5.60	0.15	103.82			

Sl No	Description of work	No	Length m	Breadth m	Depth m	Quantity	Unit	Rate in Rs	Amount in Rs
	Mukundha House Rd From end	1	82.40	4.85	0.15	59.95			
	Cross Rd-1	1	27.20	4.80	0.15	19.58			
	Cross Rd-2	1	68.20	5.20	0.15	53.20			
	Prakruthi Layout								
	2nd Cross Rd	1	42.30	5.50	0.15	34.90			
	Varadharaju Nagara								
	5th A Cross Rd	1	55.00	5.70	0.15	47.03			
	Cross Rd	1	16.70	4.85	0.15	12.07			
						1228.56	**Cum**	**7519.93**	**9238671.97**
	Approved Amount	**7519.93**							
	EIRL								
E1	Construction of granular sub-base Grading-V as Sub-base and drainage layer by providing coarse graded crushed stone aggregates of granite/ trap/basalt material, mixing in a mechanical mix plant at OMC, Carriage of mixed material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the 98 % proctor density, complete as per specifications								
	Asphalt Road								
	Edge Correction/Cut Portion								
	Singapura Paradies								
	Singapura Paradies								
	6th Main Rd	1	146.50	0.95	0.15	20.88			
	5th Main Rd	1	137.10	0.90	0.15	18.51			
	4th Min Rd	1	147.00	1.00	0.15	22.05			
	2nd Main Rd	1	161.00	1.00	0.15	24.15			
	1st Main Rd	1	165.00	1.15	0.15	28.46			
	1st Main 1st Cross Rd	1	110.50	1.10	0.15	18.23			
	1st Main 2nd Cross Rd	1	108.90	1.15	0.15	18.79			
	1st Main 3rd Cross Rd	1	125.30	1.05	0.15	19.73			
	New Sai Garden								
	4th Cross Rd	1	58.00	6.00	0.15	52.20			
	Ganesh Layout								
	3rd Cross Rd	1	120.40	2.00	0.15	36.12			
	4th Cross Rd	1	115.50	1.05	0.15	18.19			
	Main Rd	1	336.50	1.00	0.15	50.48			
	7th Main Rd	1	55.40	0.70	0.15	5.82			
	6th Main Rd Right Side Rd	1	46.20	0.70	0.15	4.85			
	6th Main Rd Left Side Rd	1	47.00	0.80	0.15	5.64			
	5th Main Rd Left Side Rd	1	36.30	0.80	0.15	4.36			
	5th Main Rd Right Side Rd	1	47.50	0.80	0.15	5.70			
	4th Main Rd Right Side Rd	1	48.90	0.70	0.15	5.13			
	2nd Main Rd Right Side Rd	1	48.90	0.80	0.15	5.87			
	Sri Balaji Layout (Singapura Bus Stop)								
	2nd Cross Rd	1	89.30	6.15	0.15	82.38			
	3rd Cross Rd Left Side Rd	1	76.60	6.50	0.15	74.69			
	3rd Cross Rd Right Side Rd	1	75.00	6.30	0.15	70.88			
	4th Cross Rd Right Side Rd	1	24.50	6.00	0.15	22.05			
	4th Cross Rd Left Side Rd	1	63.70	5.30	0.15	50.64			
	Main Rd	1	122.50	6.25	0.15	114.84			
	Singapura Layout								
	1st Cross Rd	1	70.80	0.75	0.15	7.97			

Sl No	Description of work	No	Length m	Breadth m	Depth m	Quantity	Unit	Rate in Rs	Amount in Rs
	2nd Cross Rd	1	121.30	1.15	0.15	20.92			
	3rd Cross Rd	1	185.60	1.45	0.15	40.37			
	4th Cross Rd	1	211.00	1.10	0.15	34.82			
	5th Cross Rd	1	229.50	1.00	0.15	34.43			
	6th Cross Rd From End	1	266.10	1.05	0.15	41.91			
	Cross Rd-1	1	34.70	1.10	0.15	5.73			
	5th A Cross Rd	1	96.00	0.80	0.15	11.52			
	Patanjali Shop Rd	1	141.40	1.10	0.15	23.33			
	Cross Rd-6	1	20.50	0.80	0.15	2.46			
	Cross Rd-5	1	16.00	0.85	0.15	2.04			
	Cross Rd-4	1	22.20	0.75	0.15	2.50			
	Cross Rd-3	1	24.20	0.90	0.15	3.27			
	Cross Rd-2	1	22.00	0.95	0.15	3.14			
	Cross Rd-1	1	22.70	0.90	0.15	3.06			
	3rd Main Rd	1	178.00	0.95	0.15	25.37			
	2nd Main Rd	1	395.30	0.85	0.15	50.40			
	Cross Rd-7	1	27.30	0.80	0.15	3.28			
	1st Main Rd from end	1	438.00	0.95	0.15	62.42			
	Cross Rd-8	1	27.50	0.80	0.15	3.30			
	Cross Rd-9	1	27.00	0.85	0.15	3.44			
	Kamaru House Rd	1	291.50	1.25	0.15	54.66			
	Muniswamappa Garden								
	6th Main Rd	1	208.00	1.15	0.15	35.88			
	1st Main Rd	1	112.00	1.30	0.15	21.84			
	Cross Rd-1	1	35.30	0.90	0.10	3.30			
	Cross Rd-2	1	50.00	0.80	0.15	6.00			
	Cross Rd-3	1	37.00	0.90	0.15	5.00			
	Cross Rd-4	1	51.40	0.90	0.15	6.94			
	Cross Rd-5	1	53.00	1.00	0.15	7.95			
	Cross Rd-6	1	81.70	1.00	0.15	12.26			
	Cross Rd-7	1	42.70	1.00	0.15	6.41			
	Acchi Store Rd	1	138.60	0.95	0.15	19.75			
	Kuvempu Nagara 2nd Stage								
	Thetar Gate Opposite Rd	1	73.50	1.00	0.15	11.03			
	Varadharaju Nagara								
	1st Cross Rd Left Side	1	61.00	0.90	0.15	8.24			
	1st Cross Rd Right Side	1	35.50	1.00	0.15	5.33			
	2nd Cross Rd Left Side	1	63.60	0.85	0.15	8.11			
	2nd Cross Rd Right Side	1	22.60	0.95	0.15	3.22			
	3rd Cross Rd Left Side	1	66.00	1.00	0.15	9.90			
	3rd Cross Rd Right Side	1	21.00	1.00	0.15	3.15			
	4th Cross Rd Left Side	1	65.50	0.90	0.15	8.84			
	6th A Cross Rd	1	78.00	4.15	0.15	48.56			
	4th A Cross Rd	1	81.00	5.50	0.15	66.83			
	3rd A Cross Rd	1	82.80	5.50	0.15	68.31			
	2nd A Cross Rd	1	84.00	5.25	0.15	66.15			
	1st A Cross Rd	1	71.00	4.95	0.15	52.72			
	5th Cross Rd Right Side	1	237.00	4.50	0.15	159.98			
	1st Cross A Cross Rd	1	18.00	5.25	0.10	9.45			
	Axis Bank Opposite Rd	1	152.50	4.95	0.15	113.23			

Sl No	Description of work	No	Length m	Breadth m	Depth m	Quantity	Unit	Rate in Rs	Amount in Rs
	Singapura Garden								
	4th D Cross Rd	1	119.70	1.00	0.175	20.95			
	Vasbalanagara								
	5th Cross Rd	1	144.00	1.15	0.175	28.98			
	Thirumala Store Rd	1	86.00	4.90	0.15	63.27			
	3rd Main 5th Cross Rd	1	537.50	1.85	0.175	174.02			
	Cross Rd	1	194.50	1.75	0.15	56.98			
	For CC Road								
	Naranappa Layout								
	Aniketan House Rd	1	123.60	5.60	0.15	108.50			
	Mukundha House Rd From end	1	82.40	4.85	0.10	39.96			
	Cross Rd-1	1	27.20	4.80	0.10	13.06			
	Cross Rd-2	1	68.20	5.20	0.10	35.46			
						2530.45	**Cum**	**2710.27**	**6858186.33**
	Basic Rate	**2347.00**							
	Area Weightage 10%	**234.70**							
	Sub Total 1	**2581.70**							
	Tender Permiun 4.98%	**128.57**							
	Total Rate	**2710.27**							
								Total Construction Cost	**82673784.76**

G

Assistant Engineer

Assistant Executive Engineer

Executive Engineer

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾಗ
ಬೃ.ಬೆ.ಮ.ಪಾ, ಬೆಂಗಳೂರು

ಸಹಾಯಕ ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬ್ಯಾಟರಾಯನಪುರ ಉಪ ವಿಭಾಗ
ಬಿ.ಬಿ.ಎಂ.ಪಿ, ಬೆಂಗಳೂರು-97

TEJUS CONSULTANTS

Technical Sanction
Accorded For Rs 82673784.76
Head of A/C P.3823
CER NO : 51 Dt: 10/03/2023